


# Compass® 360 Angle Mount Touch Pad


## Spare Parts Leaflet 32-AAA23500DA

February 4, 2026 / Page 1 of 5

32 A-AAA23500DA



32 A-ABA23500DA



# OTIS

This document contains technical data  
subject to EAR. ECCN: EAR99

**SERVICE ENGINEERING**  
**Otis Elevator Company**  
**Bloomfield, Connecticut USA**

Unpublished Work—© Otis Elevator Co.; 2026

# History

**32-AAA23500DA**

## Leaflet Description

This leaflet provides information for the AAA23500DA (Beijer Electronics) & ABA23500DA (BST) Compass® 360 angle mount touch pad.

## Leaflet Revisions

<b>Date Revised</b>	<b>Subject Matter Expert</b>	<b>Reason for Revision</b>
March 4, 2020	Peter DePaola	New SPL
July 14, 2021	Peter DePaola	Added Ref. 4 and 5 on p. 4
February 19, 2025	Vadzim Fedarenka	Added ABA23500DA on p.1–4; added type 3 of ADA button in table & revised note 2 on p. 3; added p. 5; added note 3 on p. 4.
February 4, 2026	Vadzim Fedarenka	Removed “Security Option” 2 from table, added Note 3 on p. 3; removed REF. No 2 on p. 4.

## Related Drawings

<b>Drawing No.</b>	<b>Title</b>	<b>Drawing No.</b>	<b>Title</b>
AAA23500DA	Compass® 360 Angle Mount Touch Pad	ABA23500DA	Compass® 360 Angle Mount Touch Pad
AAA25300AV	Compass® 360 Controller		

## Related Documents

<b>Document ID</b>	<b>Title</b>
SPL 10-AAA25300AV	Compass® 360 Controller

## Subject Matter Expert

<b>Name</b>	<b>Department</b>
Peter DePaola	Compass COE

## About Spare Parts Leaflets...

This document lists the lowest replaceable units (LRUs) for the standard version of the product. The LRUs are chosen by a team of Otis associates representing engineering and manufacturing.


While goal of this document is to make parts identification as easy as possible, the document cannot be all-inclusive. Elevator and escalator contracts classified as “special” or “custom” are not addressed here. For such contracts, please refer to specified information, the contract folder, TIPs, Field Education Articles, Construction Letters, etc. for further information.

If you have any suggestions about this document, please contact the subject matter expert listed on this page.

# Touch Pad

**32-AAA23500DA**

Numbering system (only for OSC & Berlin SSI):



**NOTE 1:** When ordering, replace the asterisks (\*) referenced in each part number with the appropriate character from the Table below.

Base Part Number			
ABA23500DA999-*-**			
Parameter Value *_*_*	Glass Color Option	ADA Button <sup>Note 2</sup>	Security Option
0	0 = Black	0 = Flat / Standard	0 = No RFID
1	1 = White	1 = CA / Angled	1 = Standard RFID
2	2 = Silver	2 = Flat / Europe	<del>2 = RFID + DirectKey Bluetooth,</del> <b>NOTE 3</b>
3	3 = Gold	3 = NYC / Three Button	3 = RFID + HID Bluetooth


**NOTE 2:** ADA type: “Standard” means the button without angle, “CA Button” means black button with a seven degree angle, “Europe” means the button color has high contrast with glass color, ‘NYC / Three Button” means 3-button arrangement required for New York City.

**NOTE 3:** ABA23500DA999-\*-\*-2 is no longer available. For replacing existing touch pad with “Security Option” 2, order ABA23500DA999-\*-\*-0 and swap out the RFID reader from old fixture to the new replacement fixture.

**Example:** ABA23500DA999-1-1-1 means this fixture type is Touch Pad, Fixture color is white, with “CA” button, with “Standard RFID reader.”

# Touch Pad

**32-AAA23500DA**



REF. No.	PART No.	DESCRIPTION	
1	AAA23851N400	Kit, Reader, RFID	See NOTE 1
2	<del>AAA23851N401</del>	<del>Kit, Reader, RFID + DirectKey Bluetooth</del>	
3	AAA23851N402	Kit, Reader, RFID + HID Bluetooth	
4	AAA23851N404	Kit, Cable, Dry Contact	See NOTE 2
5	AAA29515N2	Kit, Tools, Field Installation	

**NOTE 1: Kit includes:** RFID reader PCB, cable, and (4) M2X5 cross recessed countersunk flat head screws.




**NOTE 2: Kit Includes:** (5) Cables

**NOTE 3:** AAA23500DA Touch Pad shown on picture.

# ABA23500DA Touch Pad

**32-AAA23500DA**

## Mounting Dimensions



REF. No.	PART No.	DESCRIPTION
-	ABA23500DA999-...-...	Compass360 7" Angle Mount Touch Pad